


Notes:

1. House Service Shall Be Perpendicular To Main.
2. Reinforced Coated Tracer Wire As Manufactured By Copperhead Industries, LLC, P.O. Box 1081, Monticello, MN, 55362, Or An Approved Equal.
3. Thoroughly Tape Mechanical Connections With Electrical Tape.
4. Installation Of Sewer Lateral Into Foundation Per Town Of Easton Standards.

APPROVAL	REVISED	TOWN OF EASTON AND EASTON UTILITIES STANDARD DETAILS PVC SEWER HOUSE CONNECTION
 EU MANAGER OF ENGINEERING DATE	JUN 11,97	
	MAR 1,98	
	SEP 1,09	
	JUL, 20, 11	
	SEP 15,14	
ISSUED: JULY 1, 1996	STANDARD NO.	SS-8.02