



Notes:

1. Bedding, Haunching And Fill Material To The Top Of Pipe Shall Be Coarse Aggregate Meeting The Requirements Of AASHTO M43, Size Number 57.
2. During Haunching, Contractor Shall Carefully Work Gravel Down Around The Bottom Of The Pipe.
3. Add Detector Tape 24" Above All Pipe.

APPROVAL	REVISED	TOWN OF EASTON AND EASTON UTILITIES STANDARD DETAILS PVC SEWER MAIN TRENCH
<i>Talbot W. Bae</i> EU MANAGER OF ENGINEERING DATE	MAR 1, 94	
	AUG 1, 94	
	MAR 1, 98	
	JAN 1, 01	
	FEB 1, 06	
ISSUED: <u>MAY 1, 1989</u>	STANDARD NO.	SS-7.00